

Vol. 8.

MAY, 1921

No. 5.

JOURNAL
OF THE
BOSTON SOCIETY
OF
CIVIL ENGINEERS



Published monthly, excepting July and August, by the Society,
715 Tremont Temple, Boston, Massachusetts.

Entered as second-class matter, January 15, 1914, at the Post Office at Boston, Mass.,
under Act of August 24, 1912.

Acceptance for mailing at special rate of postage provided for in Section 1103, Act of
October 3, 1917, authorized on July 16, 1918.

Subscription Price, \$4.00 a year (Ten Numbers)
50 Cents a Copy

Copyright, 1921, by the Boston Society of Civil Engineers.

BOSTON SOCIETY OF CIVIL ENGINEERS

OFFICERS, 1921-1922

PRESIDENT

ROBERT SPURR WESTON

VICE-PRESIDENTS

FRANK M. GUNBY
(Term expires March, 1922)

EDWIN H. ROGERS
(Term expires March, 1923)

ACTING SECRETARY AND LIBRARIAN

RICHARD K. HALE

TREASURER

FRANK O. WHITNEY

DIRECTORS

JOHN E. CARTY
(Term expires March, 1922)

HENRY B. WOOD
(Term expires March, 1922)

EDGAR S. DORR
(Term expires March, 1923)

RICHARD K. HALE
(Term expires March, 1923)

PAST PRESIDENTS

(Members of the Board)

CHARLES M. SPOFFORD

LEONARD METCALF

FRANK A. BARBOUR

NOMINATING COMMITTEE

WALTER W. CLIFFORD
HARRY F. SAWTELLE
DANA M. WOOD
(Term expires March, 1922)

CHARLES R. BERRY
EDWARD S. LARNED
CHARLES R. MAIN
(Term expires March, 1923)

Past PRESIDENTS (Members of the Committee)

CHARLES R. GOW RICHARD A. HALE GEORGE C. WHIPPLE

Editor — WILLIAM L. BUTCHER
715 Tremont Temple, Boston

BOSTON SOCIETY OF CIVIL ENGINEERS
FOUNDED 1848

PROCEEDINGS

PAPERS IN THIS NUMBER.

"Construction Costs." By W. N. Connor.
Memoir of Deceased Member.

Reprints from this publication, which is copyrighted, may be made, provided full credit is given to the author and the Society.

Contributors are hereby notified that proof will not be submitted to them for examination unless requested before the 10th of the month preceding the month of publication.

MINUTES OF MEETING.

BOSTON, April 20, 1921. — A regular meeting of the Boston Society of Civil Engineers was held this evening at Chipman Hall, Tremont Temple, and was called to order at 7.50 o'clock by the President, Robert Spurr Weston.

There were 34 members and visitors present.

The President stated that, owing to illness, the Secretary would be unable to be present. Professor Spofford moved that Mr. F. I. Winslow act as Secretary *pro tem.*, and, on his declining, Mr. J. L. Howard was elected as Secretary *pro tem.*

The President gave an informal account of the meeting of the American Engineering Council held in Philadelphia.

Mr. F. I. Winslow offered the following motion:

"*Moved*: That any member of this Society who has paid the dues assessed to him for forty years shall thereafter be exempt from the payment of all dues to the Society."

On motion of Professor Spofford, the motion was amended to be referred to the Board of Government.

The President then introduced Mr. Walter E. Spear, a member of the Society, who presented a very interesting paper on the "Public Works in Modern Greece," dealing with the proposition for a water supply for Athens and Piræus, illustrated with numerous lantern slides.

After questions and discussions by Messrs. Spofford, Armstrong, Gunby and Weston, a vote of thanks was passed Mr. Spear.

The meeting adjourned at 9.30 P.M.

J. L. HOWARD;

Secretary pro tem.

APPLICATIONS FOR MEMBERSHIP.

[May 15, 1921.]

THE By-Laws provide that the Board of Government shall consider applications for membership with reference to the eligibility of each candidate for admission and shall determine the proper grade of membership to which he is entitled.

The Board must depend largely upon the members of the Society for the information which will enable it to arrive at a just conclusion. Every member is therefore urged to communicate promptly any facts in relation to the personal character or professional reputation and experience of the candidates which will assist the Board in its consideration. Communications relating to applicants are considered by the Board as strictly confidential.

The fact that applicants give the names of certain members as reference does not necessarily mean that such members endorse the candidate.

The Board of Government will not consider applications until the expiration of twenty (20) days from the date given.

KENT, ROBERT WILLARD, Newton Centre, Mass. (Age 31, b. Woonsocket, R. I.) Educated in the Woonsocket High School and Rhode Island State College, graduating in 1911 with a degree of B.S. Employed in summer vacations as follows: 1908, assistant to Master Mechanic, Manville Co.,

Woonsocket, R. I.; 1909, in United States Engineer Corps, at Newport, R. I.; 1910-11, Newport Water Works; since graduation spent three months with T. G. Hazard, Jr.; from November, 1911, to November, 1913, engineer for Fore River Ship Building Corp., Quincy, Mass.; November, 1913, to March, 1914, engineer for Newport News Shipbuilding & Dry Dock Co.; March, 1914, to October, 1916, engineer for F. A. Sayles Industrial Interests, Pawtucket, R. I.; October, 1916, to August, 1917, industrial and construction engineer for Cooley & Marvin Co., Boston; August, 1917, to February, 1919, 1st Lieutenant Ordnance Department, U.S.A.; February, 1919, to the present, construction engineer, Cooley & Marvin Co., Boston. Refers to T. G. Hazard, Jr., W. Kent, F. H. Mills, A. J. Ober, C. F. Parker, R. F. Rhodes and A. Seagrave.

MULCARE, THOMAS, Cambridge, Mass. (Age 34, b. North Adams, Mass.) Graduate of University of Vermont with a degree of B.S. in civil engineering. From July, 1909, to March, 1910, with the Springfield Water Department on the construction of Borden Brook Dam; from March, 1910, to September, 1910, with the Pittsburg Contracting Co. on the Catskill Aqueduct construction; September, 1910, to April, 1911, with the N. Y. C. & H. R. R. R. on electrical zone work at Yonkers, N. Y.; April, 1911, to February, 1912, with the Grand Trunk Pacific R. R. as resident engineer on the Regina-Moose Jaw Branch; from February, 1912, to August, 1913, and from June, 1914, to October, 1915, in the contracting business in North Adams; from August, 1913, to June, 1914, and from October, 1915, to February, 1917, with the Public Service Commission on New York City subway construction; from February, 1917, to March, 1921, with the Turner Construction Co. as superintendent, and at present in the contracting business. Refers to T. M. Beach, E. E. Lochridge, J. J. Rourke and A. G. Tomasello.

NEWSOM, REEVES J., Lynn, Mass. (Age 27, b. Columbus, Ind.) Graduated from Purdue University in 1913, followed by one year at Mass. Inst. of Tech. From May, 1914, to July, 1916, was resident engineer, Lynn Additional Water Supply; July, 1916, to January, 1918, superintendent of Water Works, Lynn. Refers to H. K. Barrows, C. B. Breed, L. Metcalf and W. L. Vennard.

VALDES, VIVIANO L., Boston, Mass. (Age 20, b. Monterey, Mexico.) Attended a preparatory school in Monterey, Mexico, 1913-1916; spent one year at the University of Notre Dame, and entered Mass. Inst. of Tech. in the fall of 1917. Refers to J. B. Babcock, G. L. Hosmer, A. P. Porter, D. Porter, K. C. Reynolds, and C. Hale Sutherland.

LIST OF MEMBERS.

ADDITIONS.

BRYANT, GEORGE L.....231 Lamartine St., Jamaica Plain, Mass.
 CONGER, ALGER A.....35 Harvard St., Worcester, Mass.
 CONNOR, BERNARD D.....77 Pennsylvania Ave., Somerville, Mass.
 MUESER, WILLIAM H.....73 Mountfort St., Boston 17, Mass.

BOSTON SOCIETY OF CIVIL ENGINEERS.

CHANGES OF ADDRESS.

BROWN, T. MORRIS.....	38 No. Burnett St., E. Orange, N. J.
CLAPP, WILFRED A.....	Care Post Quartermaster, Ft. Sheridan, Ill.
GAVETT, ANDREW J.....	312 West 5th St., Plainfield, N. J.
HORTON, FREEMAN H.....	Bradentown, Fla.
KILLION, LOUIS J.	50 East 42d St., New York, N. Y.
KIRKPATRICK, CHARLES D.....	79 Milk St., Boston, Mass.
LEAVITT, ALBERT J.....	105 Warren Ave., Hyde Park, Mass.
RICH, MALCOLM.....	316 Broadway, New York, N. Y.
STEARNS, RALPH H.....	10th Floor, 14 Wood St., Pittsburg, Pa.
WRIGHT, FRANK V.....	197 Forest St., Arlington, Mass.

DEATHS

MONAGHAN, JOHN F.....	April 18, 1921
TINKHAM, S. EVERETT.....	April 21, 1921

LIBRARY NOTES.

RECENT ADDITIONS TO THE LIBRARY.

U. S. Government Reports.

- Birth Statistics. United States Bureau of Census. 1919.
- Black Walnut, Its Growth and Management. F. S. Baker.
- Financial Statistics of Cities. 1919.
- Mineral Resources of United States. 1917. Part 1.
- Metals.
- Reconstruction and Production. Report No. 829.
- Study of California Highway System. United States Bureau of Public Roads.
- Water Supply Papers Nos. 447 and 449.

State Reports.

- Connecticut. Report of the Public Utilities Commission. 1920.
- Massachusetts. Industrial Review, No. 4. Department of Labor and Industries.
- Maine. Report of Maine Water Power Commission. 1920.
- New Hampshire. Report of Public Service Commission. September, 1916, to August, 1918.

Municipal Reports.

- Brockton, Mass. Annual Reports of Water Commissioners. 1919 and 1920.
 Burlington, Vt. Annual Report Water Department. 1920.
 Cambridge, Mass. Origin and History of Streets.
 Danvers, Mass. Annual Report of Water Commissioners. 1920.
 New Bedford, Mass. Annual Report of Water Board. 1920.
 Plymouth, Mass. Annual report of Water Commissioners. 1920.
 Reading, Pa. Annual Report Bureau of Water. 1919.
 San Francisco, Cal. Hetch Hetchy Water Supply. Report of J. R. Freeman. 1912. Gift of Stone & Webster's library.
 San Francisco, Cal. Future Water Supply. Report of Spring Valley Water Company. 1912.

Miscellaneous.

- Book of Plans, New York State Barge Canal. Gift of Clemens Herschel.
 Geographic Tables and Formulas. S. S. Gannett. Gift of H. B. Wood.
 Hydraulics of the Miami Flood Control Project. Part 7. Sherman M. Woodward.
 Location, Grading and Drainage of Highways. Wilson G. Harger. Gift of McGraw-Hill Book Co.
 Production of Coal and Coke in Canada. 1919.
 Production of Copper, Gold, Lead, Nickel, Silver, Zinc, and Other Metals in Canada. 1919.

LIBRARY COMMITTEE.

BOSTON SOCIETY OF CIVIL ENGINEERS
FOUNDED 1848

PAPERS AND DISCUSSIONS

This Society is not responsible for any statement made or opinion expressed in its publications

CONSTRUCTION COSTS.

BY W. N. CONNOR.*

(Presented February 16, 1921.)

INTRODUCTION.

THERE have been many books, pamphlets and papers published on cost accounting, but very few dealing with its application to construction work. One reason for this is that so few contractors keep a thoroughly accurate check on their costs or maintain a standard cost system. A majority rely on their bookkeeping department to furnish them cost data. This, to my mind, is doubtful practice, as a bookkeeper deals in absolutely accurate figures down to a penny, while the cost accountant's viewpoint is somewhat more liberal.

I do not mean by this that the cost accountant's figures need not check with the bookkeeper's ledger, for they must; but the training of the bookkeeper is such that he will naturally figure his costs in the same manner as he keeps his accounts, and thereby often lose the sense of proportion of costs. Costs are really tied up just as closely with the engineering and estimating departments as with the accounting department. The cost accountant should understand the physical side and be able to visualize the work itself — a thing which a bookkeeper is not trained to do.

* Chief Cost Accountant, A Berthaw Construction Company, 27 School Street, Boston, Mass.

In the introduction to the book "How to Find Factory Costs," by C. B. Thompson, occurs the following:

"The Federal Trade Commission has called attention to the fact that less than 20 per cent. of the business concerns in this country have a cost system, and that a large proportion of the many failures recorded every year is due to the absence of an accurate knowledge of what it costs to manufacture and sell. The Commission is urging every business man to take this first step in the development of that primary effectiveness by means of which alone this country can be brought to an appropriate degree of industrial preparedness."

Mr. Thompson also says:

"The chief distinction between financial accounting and cost accounting is that the former deals exclusively with the money and credit transactions of a business, while the latter deals with these same transactions but with reference to the cost of products and operations. The unit of financial accounting is the unit of money, whether the dollar, the pound, or the franc, while the units of cost accounting are the units of *money plus the units of operations*, of sales, of product and of time."

The three functions of any cost accounting system are:

1. To aid in assuring the economical handling of the work while it is in progress.

2. To obtain figures to compare with the estimate.

3. To supply data for use in estimating future work.

These are given in order of their importance.

Costs must be available at once to be effective in aiding economical handling of the work. Delayed reports of costs are practically useless in effecting any savings while the work is in progress. Proper cost reports have been compared to a fire-alarm system, in that they should not alone be able to give notice of some unusual condition but equally lead the investigation to the seat of the trouble.

Each morning the labor costs of the previous day should be known. This is not necessary or feasible on all items of work, but on such as concrete, excavation, brickwork, etc., it is possible and extremely important that the superintendent of a job should know the daily labor unit costs. If he has them he can take up with the foremen at once any variations between estimates and

actual performance, and endeavor to equalize disproportionate costs of any unit before it is too late. Prompt cost reports enable him to comment intelligently on various items before they become past history, and to be certain that both he and his foremen understand just what constitutes matters of major importance from the costs standpoint.

Only the direct labor on any operation should be included in these cost figures: that is, plant, overhead, etc., should be reported separately and not included with the direct labor charges.

By regular comparison between the actual costs obtained and the estimate, and by means of comparative statements made weekly and monthly, overruns or savings on the estimate may be discussed with the owner at once and he may be kept informed as to just how the job stands financially. This is particularly important on percentage work, as it permits the contractor and the owner to get together and talk over the progress of costs, and, if necessary, to make intelligent changes of plan while the work is under complete control and the financial bearing of changes is understood.

It used to be the custom, and I'm afraid it is yet in a good many companies, to regard costs as something to be kept secret and locked up tight, never letting the foreman know what his costs were, but always suggesting that they were excessive. How can a man be held responsible for his costs unless he is given full information regarding them while his work is in progress? And what makes for better work and loyalty then telling a man when his costs are good and commending him for the fact?

A few years ago a paper was read before this Society entitled, "Cost Accounting on Construction Work." This well-written pamphlet explained fully the system then used by the Aberthaw Construction Company for keeping costs. Since then, some changes have been made, the principal ones consisting of a change of forms, the placing of actual tabulating of the costs with the job, and the establishing of a separate cost accounting department, where before cost accounting had been a function of the estimating department.

It is difficult to make a paper interesting in which one is dealing almost entirely with figures, and I have decided that perhaps the best method is to show the various forms and explain their use and functions.

It is my intention to start with the making of an estimate and to follow through the various steps taken with an explanation of the forms used to record these cost data. I shall take up, first, the labor costs.

SECTION I.

LABOR COSTS.

1. *Summary of Estimate.*

At the start of a job an estimate is made in the usual manner. This shows the actual take-off from the plans, with the items, quantities, units and amounts. These units include the labor, material, overhead and plant costs.

FORM I.

ABERTHAW CONSTRUCTION COMPANY, BOSTON.

Job No. 1175.

November 4, 1919.

SUMMARY OF ESTIMATE.

MFG. BUILDING, TORRINGTON MANUFACTURING CO., TORRINGTON, CONN.

Concrete:

Footings, 6+13.....	19 c. y.	\$11.00	\$209
Footings, 73+126.....	199 c. y.	12.75	2 540
Columns, 101+29+50+13+27....	220 c. y.	12.75	2 795
Stairs.....	464 f. l.	1.50	696
Paving.....	748 s. f.	.22	165
Carbo. rub.....	8 000 s. f.	.08	640

Forms:

Exterior and interior footings.....	2 886 s. f.	.19½	563
Walls below grade.....	4 828 s. f.	.19½	990
Exterior columns.....	9 417 s. f.	.22½	2 120
Interior columns, metal forms.....	48 #	21.00	1 005
Floor and roof slab.....	32 042 s. f.	.17	5 450
Wall beams.....	4 212 s. f.	.23	970
Interior floor beams.....	967 s. f.	.23	222

CONSTRUCTION COSTS.

161

Reinforcement.....	110 ton	100.00	11 000
Spirals.....	1 ton	120.00	120
Excavation:			
Wall footings and int.....	660 c. y.	2.00	1 320
Backfill:			
Cinders.....	75 c. y.	2.50	188
Earth around footings.....	600 c. y.	.60	360
Steel windows:			
Sash, including glazing.....	6 300 s. f.	.69	4 342
Masonry			
Ter. a-cotta partitions			
4-in. plaster d both sides.....	5 400 s. f.	.50	2 700
6-in. { Plastered one side }.....	413 s. f.	.65	268
{ Stucco one side }			
Carpentry:			
Laying floor on tar rok.....	74 sqs.	8.00	592
2-in. spruce plank.....	16M	100.00	1 600
1-in. maple or spruce.....	9½M	90.00	855
Laying same.....	74 sqs.	.25	240
Roof over platform.....	250 s. f.	.50	125
Roofing:			
Laying tar paper.....	10 800 s. f.	.03	324
3-ply tar and gravel.....	108 sqs.	12.00	1 405
3-ply tar and gravel.....	2½ sqs.	11.00	28
Toncan metal bases and cap flashing	500 f. l.	.45	225
4-in. conductor boxes.....	5 #	20.00	100
Galvanized iron gutter.....	23 f. .	1.50	35
Flooring:			
Mastic floor.....	1 140 s. f.	.45	514
Quantities by R. L. A. Extension by R. L. A. Checked by R. L. A.			

2. Analysis of Estimate — Labor.

This estimate is then split into a labor and a material analysis. In the labor analysis these various items will show only the direct labor, with plant labor and overhead separated.

Opposite each item in the labor analysis is shown the symbol under which the working time is to be reported. This analysis is sent to the job, where it becomes the standard for labor cost comparisons on all operations of the job, and the estimate is not referred to.

One can readily see that, by separating labor and material, the work for the job superintendent in following his costs has been made much easier. He knows by the labor analysis just

what figure the Estimating Department has set for the unit on each item. He is able to study his labor costs without being obliged to figure out his material, for the cost of which he is very often not responsible, as a great deal of the purchasing may have been done at the home office. He has condensed for him now those units for which he is responsible. If he thinks any of them too low, he can take up the case at once with the Estimating Department — and I must confess that this is done quite often.

FORM II.

ABERTHAW CONSTRUCTION COMPANY.

Job No. 1175.

January 8, 1920.

ANALYSIS OF ESTIMATE.

LABOR.

Code		EXCAVATION.		
Di	Pumping.....			\$200
Das	Clear site.....			100
Dad	Excavate for footings.....	800 c. y.	\$1.70	1 360

PLANT.

Pel	Towers and hoists	415	}	
Pen	Temporary buildings	415		
Pem	Mixer, motor and pits	205		
F Pes	Sawmill	130		
Per	Access runs and staging	250		1 895
Pe	Miscellaneous plant	130		.75T
Pu-T	Teaming plant	75T		
Pu	Unload	245		
Peb	Boiler and shack	105		

FORMS.

Fac	Exterior columns.....	Make	31 sqs.	4.95	154
Fec		Erect	62 sqs.	10.65	660
Fic		Strip	62 sqs.	2.30	143
Fawb	Wall beams and pilas-				
	tered.....	Make	20 sqs.	3.20	64
Fewb	parapet	Erect	42 sqs.	12.50	525
Fiwb		Strip	42 sqs.	2.30	97

STEEL.

Ru	Unload reinforcement.....	114 tons	2.30	262
Ru-T	Team.....	114 tons	.55	63T
Rac	Cut and bend col. steel.....	27 tons	3.55	96
Rec	Place col. steel.....	30 tons	8.55	257

CONCRETE. — Mix and Place.

Med	Footings, piers and pipe supports	306 c. y.	1.45	444
Mep	Paving.....	12 c. y.	1.80	22
Mef	Exterior and interior columns, floor and roof slabs, wall beams and interior floor beams, including patch and first rub.....	1 020 c. y.	2.05	2 095
Mecw	Curtain walls.....	100 c. y.	6.70	670
Mux	Unload and handle cement....	3 400 bbls.	.16	544
Mux-T	Team cement.....	3 400 bbls.	.11	374T
Muy	Trim sand stock pile.....	850 c. y.	.085	72
Muz	Trim stone stock pile.....	2 020 tons	.085	172

OTHER TRADES.

Sew	Set and point steel sash.....	6 800 s. f.	.62	422
Tef	Lay Tar Rok floor 1 in. thick..	76 sqs.	4.40	334
Ced	Setting doors and hardware....	* 26	9.75	253
Glew	Glazing sash.....	3 200 lts.	.0975	312
W	Watchman.....			500
O	Job overhead.....			1 700
Mh	Cold weather expense.....			2 500

3. *Timekeeping Symbols.*

Most contractors use a series of numbers for reporting their labor operations, but Aberthaw uses a mnemonic code.

In the Aberthaw system the first letter is always a capital and indicates the kind of work to be done. For instance, —

F stands for Forms,
R for Reinforcement,
B for Brick,
D for Digging, etc.,

in so far as possible the first letter of the item represented being used. The second letter is always a vowel and explains the class of the work.

a stands for making items,
e for erecting or setting up,
i for tearing down or dismantling,
o for repairing,
u for unloading.

The third letter, which is always a consonant, indicates the part of the building in which the work is being executed, as —

f floor,
w walls,
c columns,
s stairs.

As the code is the same on all jobs, our timekeepers and cost men quickly adapt themselves to any requirements of the work. If some work comes up not included in the code, a timekeeper can very quickly make up his symbol to cover it, and it can usually be interpreted by the cost man. If necessary, an explanation may be written opposite the item the first time it is reported.

A real feature of this code is the manner in which it helps visualize the work. For instance, with numbers one might have 21.1 as a symbol for erecting brick walls. How much better is the symbol Bew, — “ B ” brick, “ e ” erect, “ w ” walls.

FORM III.

STANDARD SYMBOLS

Flat Slab	Make	Erect	Strip	Report
Floor and roof slab panels, wood.....	Fafw	Fefw	Fif	Square feet
Floor and roof slab girts.	Fafg	Fefg	Fif	Lineal feet
Floor and roof slab joists.	Fafj	Fefj	Fif	Lineal feet
Floor and roof slab panels, metal.....	Fafm	Fefm	Fifm	Square feet
Plinths.....	Fafp	Fefp	Fifp	No. and sq. feet
Floor and roof slab mud sills.	Fafs	Fefs	Fif	Lineal feet
Floor and roof slab posts....	Fafv	Fefv	Fif	Number
Flat slab, inclusive.....	Faf	Fef	Fif	Square feet
Beam and Girder				
Floor beams and panels, in- clusive.....	Fafb	Fefb	Fifb	Square feet
Gutters and open drains.	Fag	Feg	Fig	Square feet
Cornice, coping and belt course	Fak	Fek	Fik	Lineal feet
Stairs.....	Fas	Fes	Fis	{ Lin. ft. of stairs and sq. ft. of landings.
Tunnel walls and ceilings....	Fat	Fet	Fit	Square feet
Walls.....	Faw	Few	Fiw	Square feet
Walls erected between slabs, columns or walls previously poured.....	Fawp	Fewp	Fiwp	Square feet

Wall beams, erected with slabs

and columns. **Fawb** **Fewb** **Fiwb** Square feet

Threading and rethreading bolts to be charged to "e" symbol on which used.

4. *Timekeeper's Field Sheet.*

To report the time and distribution of the men, the timekeeper uses a field sheet which shows each man's number in the left-hand column.

These sheets are in two series, one running from 0 to 50, and the other from 51 to 100, and the numbers are printed on the sheets, so that if a job has a series of checks numbered from 1 200 on, the timekeeper needs only to write in the number 12. The next columns show the time at which the men reported for work and the time at which they quit work.

Then there are eleven columns, each one representing one hour's work, and headed 7-8, 8-9, 9-10, etc., up to 5-6. In these spaces, after each man's number is written the symbol for the type of work performed. If one man is erecting forms from 7 to 12 continuously, the symbol "Fef" would appear in the first hour column and a dash in each succeeding column up to 12 o'clock. Then he might change and work at erecting wall forms to 5 o'clock. In such case the symbol "Few" would show. The timekeeper makes four checks a day, and if the men have changed their class of work between checks, he confers with their foremen as to the hour when changes have been made. The remaining columns show the rate, then the amount earned and the actual hours worked divided into regular and overtime.

We have, therefore, on this timekeeper's field sheet a complete record of each man's daily time and class of work performed.

This field sheet is the same length and ruled the same as is the pay-roll sheet. We can, therefore, in transferring the time from this field sheet to our pay roll, simply lay it down on the pay-roll sheet and copy the figures on the lines which coincide. This offers a great saving of time and is much more accurate than calling the time off, or transferring it by comparing the men's numbers.

The type of ruling on forms is a very important item. Those forms which are to be used together should be, in so far as

ABERTHAW CONSTRUCTION COMPANY.

Job No. 1175.

Date, 12-27-19.

AT TORRINGTON, CONN.

Timekeeper's Name, H. W. Murdick,

Sheet No. 1.

MAN'S No.	IN A.M.	IN P.M.	OUT.			IN P.M.	— 12.	— 1 P.M.	— 2.	— 3.	— 4.	— 5.	— 6.	RATE.	AMOUNT.	TIME.	
			7	8.	9.											Reg.	Over.
Kinsley	2201	7	..	5	0	..					...	..	..	\$39.00	\$6.50	9	
Hollen	02	7	..	5	Raf	..			Ref		Rec	..	..	40.00	6.67	9	
Howard	03	7	..	5	Fec	..					..	..	..	48.00	8.00	9	
Murdick	04	7	..	5	0	..					..	..	..	21.00	3.50	9	
Zavrello	05	7	..	5	Dad	..			Mux		Ded	..	..	39.00	6.50	9	
	06	7	..	5	Fec	..			Fedw			..	..	.85	7.65	9	
	07	7	..	5	Fec	..						..	..	.85	7.65	9	
	08	7	..	5	Fec	..						..	..	.85	7.65	9	
	09	7	..	5	Fec	..						..	..	.85	7.65	9	
	2210	7	..	5	Fec	..						..	..	.85	7.65	9	
	11	7	..	5	Fec	..						..	..	.85	7.65	9	
	12	7	..	5	Fec	..						..	..	.85	7.65	9	
	13	7	..	5	Fec	..						..	..	.85	7.65	9	
	14	7	..	5	Fec	..						..	..	.85	7.65	9	
	15	7	..	5	Fec	..						..	..	.85	7.65	9	
	16	7	..	5	Fec	..						..	..	.85	7.65	9	
	17	7	..	5	Fec	..						..	..	.85	7.65	9	
	18	7	..	5	Fec	..						..	..	.85	7.65	9	
	19	7	..	5	Fec	..						..	..	.85	7.65	9	
	2220	7	..	5	Raz	..			Ref			..	..	.55	4.95	9	
	21	7	..	5	Raz	..			Ref			..	..	.55	4.95	9	
	22	7	..	5	Rec	..			Ref			..	..	.55	4.95	9	
	23	7	..	5	Rec	..			Ref			..	..	.55	4.95	9	
	24	7	..	5	Rec	..			Ref			..	..	.55	4.95	9	
	25	7	..	5	Rec	..			Ref			..	..	.55	4.95	9	

possible, ruled similarly. This fact I do not believe is usually given the emphasis that it deserves.

5. *Waste Sheet.*

The office cost man, with the timekeeper's field sheets before him, now uses a sheet which is called a "Waste Sheet." He combines all the "Fef," "Med," "Ref," etc., symbols of the Field Sheet and figures the total daily expenditure under each symbol. These amounts he enters each in a column headed with its proper symbol. The total should check with the total daily pay roll.

This sheet is ruled for seven days. It is kept up to date daily, so that at the end of the week the cost man has the total weekly expenditure for all the symbols under which work has been performed. The quantity man gives him the quantity of work accomplished, which he enters under the total weekly cost of the "Waste Sheet" and then figures the unit cost and writes that under the quantity. He then has under each symbol the total weekly expenditure, weekly quantity, and weekly unit.

6. *Labor Cost Record.*

The next step is to transfer these items to the Unit Cost Record Book. This is a loose-leaf, I. P. ring binder, carrying a sheet for each symbol. The first column of the sheet shows the date of the week ending; the second the weekly cost, the third the weekly quantity, and fourth the weekly unit. These items take up about one half the sheet. The other half shows the cost to date, quantity to date, and unit to date. As a partial check on these items there are included two columns, one for number of barrels of cement used, and one for cubic feet of concrete per barrel. At the top of the sheet, directly over the quantity, amount and unit to date column, is a space to write in the estimated quantity, amount and unit, so that these estimated figures can be compared with the actual figures at any time.

This is kept up to date each week, and is checked against the total pay roll of the job. This book is the permanent record of the labor costs and is sent to the home office at the completion of the job.

CONSTRUCTION COSTS.

169

FORM V

Job No 1175

WASTE SHEET

WEEK ENDING 1-6-20

DATE	DND	DNDP	DEOP	FEC	FIC	FACW	FECW	FAD	FAD	FEC	FIC	FAB	FACB	FIMB	GEW
12-31-19	10.25	77.90		30.00	12.00	8.40		17.95	74.95	32.00		12.48	8.25		8.50
1-1-20		55.55	7.40	32.85	15.45	7.65			82.10	31.50	14.50	17.50	13.00		8.50
1-2-20		57.20	9.00	27.50	17.20	9.20			78.80	31.99		12.00	10.30		10.20
1-3-20	6.00	60.63		30.42	14.85	7.85			69.03	33.60		11.05	5.75		9.75
1-4-20															
1-5-20		75.35	5.40	27.58	19.00		5.00		80.15	29.00		9.00	8.25		9.75
1-6-20		61.00		26.00	12.60		6.45	10.25	88.00	32.10		17.50	1.00		6.38
TOTAL	16.25	390.13	21.80	174.35	91.10	7.85	43.55	10.25	17.95	465.03	190.19	14.50	76.53	45.55	53.08
QUANTITY	864	24024	6124	16239	35659	1259	4239	1959	1959	10539	70719	4759	7439	15749	22034
UNIT	2.03	1.63	.36	10.75	3.57	6.15	10.25	5.51	9.65	5.14	2.69	3.10	10.30	2.90	.24

DATE	MECN	MEB	MEF	MH	MNY	O	PE	PEL	REC	REC	RAR	PER	SEP	SEV	TOTAL
12-31-19		4.10	141.61	50.30		15.41	7.70	3.50	5.06	11.45	8.40	2743		15.60	583.24
1-1-20	18.50	3.00	16.814	54.90		15.41		8.00	4.23	12.16	9.23	31.80		9.75	617.12
1-2-20	9.00	4.60	176.23	53.10	11.00	15.41		2.00	5.73	9.81	8.80	2410			585.17
1-3-20	2.50	1.55	86.64	48.60		15.41		2.00	7.10	10.43	10.15	2948		6.29	474.82
1-4-20															
1-5-20		4.60	73.22	61.33		15.41		1.00	3.10	8.63	9.41	32.46		11.40	509.54
1-6-20			40.72	62.65		15.41			2.20	15.60	7.26	15.33			412.45
TOTAL	30.00	17.85	765.96	320.88	11.00	92.46	7.70	16.50	27.42	68.07	53.25	160.60		21.15	3182.34
QUANTITY	1424	264	21824		9854				87	97	11.7	18.7		700*	
UNIT	2.14	2.55	3.24		.112				3.43	7.56	4.84	8.92		.031	

Overall w/E 1-6-20 = 82182.34

7. *Labor Cost Statement.*

We are now ready to make out the Weekly Labor Cost Statement. In this, first the symbol is shown, then the kind of work; next, the weekly cost and weekly unit. Succeeding columns offer a detailed comparison with the Analysis of Estimate, — the estimated quantity unit and cost being set against the actual quantity and unit and cost attained in operation. The last two columns give opposite each item, in one case, the overrun; in the other, the saving.

As an illustration:

Suppose we have listed in our analysis of estimate 1 000 cu. yds. of concrete under the symbol "Med," at a unit cost of \$1.50 per cu. yd. By the fifth week of the job there has been completed 700 cu. yds. at a unit cost of \$2.00 per cu. yd. Seven hundred cubic yards at \$1.50 would be \$1 050, which would have been the expenditure on that item, provided the work had been done at the estimated unit of \$1.50. But actual cost is \$2.00 per cu. yd., which means an expenditure of \$1 400, or an overrun of \$350 on this item. If it had been done for a unit of \$1.00, there would have been a saving of 50 cents per cu. yd., or a total saving to date of \$350. Each item is figured out similarly, and the difference between the saving and overrun is shown in the proper column.

For those items on which no quantity is reported, as plant, watchman, overhead, etc., a percentage is used. For example, if \$1 000 is allowed for overhead and the job is to last ten weeks, this overhead will average \$100 per week. If, after the job has gone six weeks and \$700 has been expended, and it is figured that \$450 more will be expended, the overrun will be \$150; and this is shown.

The labor cost sheet gives the costs in detail for the job superintendent to study, and informs him just where he should concentrate and what he should study. If 75 per cent. of his total overrun is in two items, the place for him to remedy his high units is clear. Without some such data how can a superintendent intelligently talk to his foremen or know his job?

FORM VII.
ABERTHAW CONSTRUCTION COMPANY.
AT TORRINGTON, CONN.

Job No. 1175.

LABOR STATEMENT TO DECEMBER 23, 1919. — 8TH WEEK.

Sheet No. 1.

ITEM.	QUANTITY.		UNIT.		COST.		SAVING.	OVERRUN.
	Estimate.	Actual.	Estimate.	Actual.	Estimate.	Actual.		
EXCAVATION.								
Das	\$	100			83	83	683	
Dad	c. y.	800	702	1.70	1 193	948		
Ded	c. y.	950	331	.83	275	179		
Dadp	c. y.	1 030	931	1.70	1 583	1 378		
Dedp	c. y.	980	442	.83	367	230		
PLANT.								
Pe	\$	1 895			3 501	2 818		242
FORMS.								
Fed	sq.	39	36	10.50	378	321	19	
Fadw	sq.	52	52.7	2.65	140	202		
Fedw	sq.	78	78.7	10.50	826	769		
Fidw	sq.	78	30.2	3.15	95	84		
Faf	sq.	110	74	2.75	204	209		
Fef	sq.	320	41	5.50	225	317	136	
Ful	M	96	47	2.30	108	93		
REINFORCEMENT.								
Raz	t.	26	16	4.10	1 976	1 995		
Rez	t.	26	14	14.10	66	180		
					197	219		
					263	399		

[illegible]

8. *Labor Comparison.*

In order to condense this report for the management, a comparison of savings and overruns is made, listed under the various symbols. All the overruns or savings on one class of work are totaled, and the total overrun or saving shown as concrete, forms, reinforcement, etc. The record of the previous week is also shown so it may be compared with that of the current week.

The Labor Cost Statement, together with this labor comparison sheet attached, is sent into the main office each week so as to reach there not later than the Monday morning following the closing of the pay roll. One copy goes to the general superintendent and one to the Cost Department.

9. *Pay-Roll Sheet.*

The pay-roll sheet is ruled for seven days, with two columns for each day, — one to show regular and the other overtime hours. The regular and overtime hours are extended and shown in separate total columns, as also is the regular and overtime rate, the total amount earned for the week being in the next column.

The man's name and number appear in the extreme right-hand column. This, I think, is rather unusual, but we find it much better when paying off, as the person paying need only look at the next column and not from one side of the sheet to the other to check the name and amount, which lessens the danger of errors considerably.

So much for the labor cost records. Their handling is so standardized that we can transfer our cost men, if necessary, to any job, and they can readily pick up another timekeeper's or cost man's duties.

175

ABERTHAW CONSTRUCTION COMPANY

20th Week

	W/E 7-13-20		W/E 7-20-20	
	Saving	Overrun	Saving	Overrun
Concrete	5214		5982	
Plant		883		1079
Forms		2877		4426
Reinforcement		79	118	
Excavation		4095		5666
Masonry	1228		1474	
Carpentry		1597		1606
Ironwork		199		243
Sash				
Painting				
Overhead, etc.				
Miscellaneous				
	6442	9730	7574	13019

Labor " to 7-13 1920 - \$ 3288.

Total	"	"	\$105885.68
-------	---	---	-------------

FORM IX.

ABERTHAW CONSTRUCTION COMPANY.

Job No. 1175.

PAY ROLL.

AT TORRINGTON, CONN.

	Wed. 24.	Thurs. 25.	Fri. 26.	Sat. 27.	Sun. 28.	Mon. 29.	Tues. 30.	HOURS.		
								R.	O. T.	S.
1	9		9	9		9	9	1 wk.		
2	9		9	9		9	9	1 wk.		
3										
4										
5	9		9	9		9	9	1 wk.		
6	9		9	9		9	9	1 wk.		
7										
8	9		9	9		9	9	1 wk.		
9										
10										
11	9		9	9		9	9	1 wk.		
12										
13										
14	9		9	9		6 $\frac{1}{2}$	9	42 $\frac{1}{2}$		
15	9		9	9		9	9	45		
16	9		9	9		9	9	45		
17	9		9	9		9	9	45		
18	9		9	9		9	9	45		
19	9		9	9		9	9	45		
20										
21	9		9	9		9	9	45		
22	9		9	9		9	9	45		
23	9		9	9		9	9	36		
24	9		9	9		9	9	45		
25										
26	9		9	9		7	9	43		
27	9		9	9		9	9	45		
28	9		9	9		9	9	45		
29										
30										
31										
32	9		9	9		9	9	45		
33	9		9	9		6	9	42		
34	9		9	9		9	2	38		
35	9		9	9		9	9	45		
36	9		9	4		9	9	40		
37	9		9	9		9	9	45		
38	9		9	9		8	9	44		
39	9		9	9		9	9	45		
40										
41										
42										
43										
44										
45										
46										
47										
48										
49										
50										
	243		234	238		234 $\frac{1}{2}$	236	1 185 $\frac{1}{2}$		

Sheet made out by H. W. Murdick.
Checked by H. S. Kinsley.

ABERTHAW CONSTRUCTION COMPANY.

Page 1.

PAY ROLL. — CONTINUED.

From 12-24-19 to 12-30-20.

	RATE.			AMOUNT.	DATE Pd. Off.	MAN'S NO.
	R.	O. T.	S.			
1				Pd. by B. O.		Supt. 2201 Richardson
2	\$39.00			\$39.00		Clerk 02 Kinsley
3						03
4						04
5	40.00			40.00		Steel Fore. 05 Hollen
6	48.00			48.00		Carp. Fore. 06 Howard
7						07
8	21.00			21.00		Timekeep. 08 Murdick
9						09
10						2210
11	39.00			39.00		Lab. Fore. 11 Zavrello
12						12
13						13
14	.85			36.13		Carp. 14
15	.85			38.25		Carp. 15
16	.85			38.25		Carp. 16
17	.85			38.25		Carp. 17
18	.85			38.25		Carp. 18
19	.85			38.25		Carp. 19
20						2220
21	.55			24.75		Steel 21
22	.55			24.75		Steel 22
23	.55			19.80		Steel 23
24	.55			24.75		Steel 24
25						25
26	.70			30.10		Mech. 26
27	.70			31.50		Mech. 27
28	.70			31.50		Mech. 28
29						29
30						2230
31						31
32	.50			22.50		Labor 32
33	.50			21.00		Labor 33
34	.50			19.00		Labor 34
35	.50			22.50		Labor 35
36	.50			20.00		Labor 36
37	.50			22.50		Labor 37
38	.50			22.00		Labor 38
39	.50			22.50		Labor 39
40						2240
41						41
42						42
43						43
44						44
45						45
46						46
47						47
48						48
49						49
50						2250

Approved, W. E. Richardson, Supt.

Approved, Inspect.

Page total, \$773.53.

SECTION II.

MATERIAL COSTS.

1. *Purchase Order.*

The first form necessary, of course, for material records is the Purchase Order. This form is made to give all the necessary information and to show what the material is to be used for which gives the cost man his distribution.

2. *Material Received Form.*

On receipt of the material, it is checked and entered on the Daily Material Received Form, showing the order number, vendor and material. On receipt of an invoice it is checked against this material received sheet for receipt of the goods.

3. *Invoice Record.*

When the invoice has been approved and passed for payment it is entered in the Invoice Record. There is a page here for each vendor, and all payments made are entered, showing the invoice number, commodity and amount. In the right-hand columns are shown the check number with which the invoice was paid, date and voucher number. The last column shows the statement number on which the invoices appear when the month's expenditures are reported to the owner.

A page is also used for the weekly pay rolls, and this register should check with the total of the Labor and Material Cost Books.

4. *Analysis of Estimate — Material.*

As stated previously, the Summary of the Estimate is divided into the Labor and Material Analyses. The Material Analysis shown here includes all the material to be used on the job, with the quantities, unit prices and total money; also the subcontracts, insurance and field office equipment.

This analysis is used for all material cost comparisons and by the Purchasing Department in checking up their purchases and prices submitted.

Form 53E. 9-24-19

ABERTHAW CONSTRUCTION COMPANY, AGENT
BOSTON, MASS.

VENDOR'S COPY

Job No. _____
Order No. **E4753**

To be
Marked on
Invoice

PURCHASE ORDER

Date _____ 191

TO _____	Ship to ABERTHAW CONSTRUCTION COMPANY, Agent
_____	Address _____
_____	Via _____
_____	You agree to make shipment _____
_____	From your STOCK—MILL—FACTORY _____
_____	At _____

Invoice to _____
ABERTHAW CONSTRUCTION COMPANY, Agent
Mail Invoice to **ABERTHAW CONSTRUCTION COMPANY, Agent**
Address _____
SEND INVOICE IN TRIPLICATE and address all correspondence as above

Please furnish the following :

PRICE _____	USED FOR _____	Bldg. _____
F. O. B. _____	RECEIVED _____	Req'n No. _____ Auth'n No. _____
TERMS _____	BILL REC'D _____	Bill O.K.'d _____

We reserve the right to cancel in case of delay

Although the principal is solely responsible for the payment of materials and services furnished hereunder, the seller may with respect to materials and services so furnished deal with Abertshaw Construction Company as agent for said principal.

Owner's Name _____
By **ABERTHAW CONSTRUCTION COMPANY**
Agent

This confirms our mutual _____ agreement By _____

DETACH, SIGN AND RETURN ACCEPTANCE BELOW BY NEXT MAIL

ACCEPTANCE

Owner's Name _____ Date _____ 191

ABERTHAW CONSTRUCTION CO., Agent

We accept your Order No. **E4753** dated _____ on your Form _____

FORM 179

ABERTHAW CONSTRUCTION COMPANY

MATERIAL RECEIVED

JOB NO. 1175

AT Torrington Conn

DATE December 27 1919

ORDER NUMBER	DESCRIPTION	QUANTITY	FROM WHOM RECEIVED	DATE INVOICED	HOW DELIVERED	CHARGES	REMARKS IF CHARGES ARE TO MERCHANT NOTE IN THIS COLUMN
D 11944	Gravel	20 yds	Torrington Bldg. Co.	1/3	Truck		
E 6950	"	15 "	F. W. Fuller	1/6	"		
"	Sand	12 "	"	1/6	"		
D 11977	12" Hack saw Blades	12	W. H. Morrison		Messenger		
D 11978	Sledge Hammer Handles	6	Lyford Howe Co.		"		
"	8" Flat Files	6	"		"		
E 3619	Oregon Cement	231 bbls	Portland Stone Ware		Freight C846 1322.08		

SIGNED ABERTHAW CONSTRUCTION CO.

H. S. Kinsley

SECTION II. — FORM III.

PAGE 52

INVOICE RECORD

VENDOR Patland Stowers CoJob No. 1177

INVOICE NO.	DATE	MATERIAL	GROSS AMOUNT	DEDUCTIONS	DISCOUNT	NET AMOUNT	CREDITS	CHECK NO.	DATE OF CHECK	VOUCHER NO.	STATE NO.
36	11-20-19	Cement	652.12		11.90	640.22		44	11-28-19	10	2
46	11-24-19	"	474.02		8.65	465.37		63	12-5-19	10	3
152	12-8-19	"	474.02		8.65	465.37		113	12-16-19	10	4
163	12-10-19	"	822.00		15.00	807.00		123	12-19-19	10	5
188	12-24-19	"	643.90		11.75	632.15		143	12-24-19	10	6
189	12-24-19	"	424.02		8.65	415.37		143	12-24-19	10	6
201	12-26-19	"	685.00		12.50	672.50		188	1-5-20	10	7
222	12-26-19	"	657.60		12.00	645.60		192	1-7-20	10	7
242	12-28-19	"	641.16		11.70	629.46		203	1-8-20	10	7
246	12-28-19	"	632.94		11.55	621.39		203	1-8-20	10	7
260	12-31-19	"	474.02		8.65	465.37		216	1-13-20	10	8
261	12-31-19	"	800.08		14.60	785.48		216	1-13-20	10	8
277	1-2-20	"	474.02		8.65	465.37		216	1-13-20	10	8
278	1-2-20	"	679.14	267.35	11.55	400.24		222	1-14-20	10	8
279	1-6-20	"	643.90		11.75	632.15		232	1-14-20	10	8
287	1-6-20	"	394.56		7.20	387.36		240	1-20-20	10	9
C.V. 1	2-26-20	" Job 1178					226.25			1	
C.V. 10	4-10-20	" Bags					538.60	Check paid to cover			24
C.V. 15	6-7-20	" "					31.13	"	"	"	29

CONSTRUCTION COSTS.

181

SECTION II.—FORM IV.

ABERTHAW CONSTRUCTION COMPANY.

Job No. 1175.

January 8, 1920.

ANALYSIS OF ESTIMATE.

MATERIALS AND SUBCONTRACTS.

Cement.....	3 400 bbls.	\$2.29	\$7 790
Freight and loss on empties.....	3 400 bbls.	.05	170
Tests.....	3 400	.02½	85
Sand.....	3 850 c. y.	2.00	1 700
Gravel.....	1 500 c. y.	2.50	3 750
Peastone.....	50 tons	2.50	125
Cinders.....	220 c. y.	1.50	330
Plant:			
Small tools and supplies	}		
Rental for mixer, motor, joists, towers			
Power and fuel			
Temporary buildings			
Stagings, ladders and runs			2 300
Sawmill			
Form lumber, 95M (less salvage).....			5 000
Nails, oil and sundries.....			375
Metal forms erected.....	# 48	18.30	875
Lumber, 2-in. spruce planks.....	17M	65.00	1 105
3-in. planks.....	1½M	65.00	87
¾-in. furring	}		
2 x 4 studding			
¾-in. tongue and groove			50
1-in. maple flooring.....	10M	92.00	920
1-in. cork flooring.....	68 s. f.	.44	30
1-in. cell board.....	135 s. f.	.38	50
Building paper.....	76 rolls	3.50	266
Stair rail.....	80 ft.	1.00	80
Steel reinforcement.....	111 tons	80.00	8 880
Steel spirals.....	4 tons	100.00	400
Steel sash.....	6 800 s. f.	.353	2 400
Glass.....	6 100 s. f.	.13	800
Putty for glazing.....	3 200 lbs.	.06	192
Lime.....	4 tons	22.00	88
Terra-cotta blocks, 4 in.....	5 400 s. f.	.12	648
Terra-cotta blocks, 6 in.....	1 080 s. f.	.15	162
Nonpareil insulating brick, 4 in.....	200 s. f.	.40	80
Nonpareil insulating brick, 2½ in.....	160 s. f.	.30	48
Akron Tile Pipe, 8 in.....	290 fl.	.30	87
Akron Tile Pipe, 6 in.....	60 fl.	.20	12
Akron Tile Pipe, 5 in.....	50 fl.	.20	10

SECTION II. — FORM IV. CONTINUED

Metal lath.....	8 s. y.	\$1.30	\$10
Sundry plaster materials.....			25
Freight elevator.....			3 475
Electrical contract.....			2 300
Heating and sprinkler contract.....			12 962
Plumbing.....			3 500
Cold weather materials.....			1 000
Liability insurance.....			1 500
Superintendent's salary, travel, board, stationery, office, etc.....			1 600

5. *Material Cost Record.*

The Material Cost Record consists of a loose-leaf I. P. binder book. In it each item in the Material Estimate has a page, and the estimated quantity, amount and unit is entered at the top of the sheet. After the invoices for material have been checked and paid they are entered in the Material Cost Record. The date of the invoice, vendor's name, kind and amount of material, and cost, are entered.

There is also a column headed "Outstanding Orders," and the amount of an order, as soon as it is placed, is shown in this column in pencil. As payments on these orders are made they are entered in ink in the amount column, and the outstanding order figure reduced correspondingly. The next column is for credits and the last shows the total cost.

This book, then, contains all amounts paid for material on the job, and the total of this book and the labor cost record at the completion of the work must check with the total cost as shown in the bookkeeper's ledger. This book is the permanent record of the material costs, and is sent to the home office at the completion of the job.

6. *Material Cost Statement.*

In order to know how our purchases for material compare with the analysis of estimate, we make each month a Material Cost Statement similar to our Weekly Labor Cost Statement and show the overruns or savings on each item.

This form shows the item first, then the estimated and actual quantity, estimated and actual unit and estimated and actual cost. In the next column is entered the outstanding

SECTION II.—FORM V.
MATERIAL COST RECORD.

Job No. 1175.

Item, Form Lumber.
Estimated

Unit.

5,000

91M.

\$55.00

Date.	Bought from	Amount and Description.	Cost.	Out- standing Orders.	Credits.	Cost to Date.
11-17-19	Torrington Building Co.	2 000' 4 x 4 chestnut, 125/12'				
		720' 3 x 4 chestnut, 60/12'				
		2 038' 4 x 4 chest, 36/10, 81/12 and 14/14	\$199.82			
11-18-19	J. C. Iffland Lumber Co.	4 010' 2 x 6 N. C. pine				
		2 502' 1 x 8 N. C. roofers				
		1 070' 3 x 4 chestnut				
		910' 4 x 4 chestnut, oak and hemlock	424.82			\$624.64
11-22-19	J. C. Iffland Lumber Co.	20 707' 1 x 6 N. C. roofers	978.87			1 603.51
11-29-19	J. C. Iffland Lumber Co.	1 086' 1 1/4 x 6 spruce, D4S	75.26			1 678.77
		756' 2 x 4 x 18 rough spruce				
		1 122' 3 x 6 rough spruce				
		476' 4 x 6 rough spruce				
		1 206' 2 x 6 x 18 S2E spruce				
		2 016' 2 x 6 x 18 S2E spruce	386.42			2 065.19
12-1-19	J. C. Iffland Lumber Co.	13 603' 3 x 4, 2 x 6, 3 x 6 rough and S2E spruce	942.69			3 007.88
12-2-19	J. C. Iffland Lumber Co.	4 779' 3 x 4, 2 x 6, 3 x 6 D2E spruce	331.18			3 339.06
12-3-19	J. C. Iffland Lumber Co.	3 217' 1 x 6 N. C. roofers	175.17			3 514.23
		7 074' 6 x 6, 3 x 6, 1 x 6, 2 x 3, 2 x 6 and 1 1/4 x 4 rough spruce	490.23			4 004.46
12-4-19	J. C. Iffland Lumber Co.	3 130' 3 x 6, 3 x 8, 1 1/4 x 4 rough spruce	216.91			4 221.37
12-5-19	J. C. Iffland Lumber Co.	5 375' 1 1/4 x 4, 1 1/4 x 8, 1 x 6, 3 x 4 and 3 x 6 rough spruce	372.49			4 593.86
12-8-19		1 626' 1 1/4 x 6 D4S spruce				

CONSTRUCTION COSTS.

185

12-8-19	J. C. Iffland Lumber Co.	1 216' 3 x 4 and 1 1/4 x 4 spruce	\$196.95		\$4 790.81
12-9-19	J. C. Iffland Lumber Co.	2 193' 1 1/4 x 6 D4S spruce	151.97		4 942.78
12-12-19	J. C. Iffland Lumber Co.	340' 1 1/4 x 8 D4S spruce			
		639' 1 1/4 x 6 D4S spruce	67.84		5 010.62
		1 190' 1 1/4 x 8 D4S spruce			
12-13-19	J. C. Iffland Lumber Co.	571 1 1/4 x 6 D4S spruce	122.04		5 132.66
12-15-19	J. C. Iffland Lumber Co.	508' 2 x 6 N. C. pine	29.67		5 162.33
		115' 1 1/4 x 4 D4S spruce	7.97		5 170.30
		366' 2 x 3 D4S spruce			
		476' 3 x 4 x 14' D2E spruce			
12-24-19	J. C. Iffland Lumber Co.	468' 3 x 6 D2E spruce	90.78		5 261.08
12-11-19	J. C. Iffland Lumber Co.	2 010' 1 x 6 rough boards	69.65		5 330.73
3-31-20	Torrington Mfg. Co.	1 228' 1 1/4 x 6 D4S spruce	85.10		5 415.83
3-30-20	A. C. Co.	55 000 salvage, lumber at \$35 per M		\$1 925.00	3 490.83
		P. C. salvage on lumber		17.00	3 473.83

SECTION II.—FORM VI.

ABERTHAW CONSTRUCTION COMPANY.

AT TORRINGTON, CONN.

Job No. 1175.

MATERIAL STATEMENT TO FEBRUARY 2, 1920.

Sheet No. 1.

ITEM.	QUANTITY.		UNIT.		COST.		OUT- STANDING ORDERS.	SAVING.	OVERRUN.
	Estimate.	Actual.	Estimate.	Actual.	Estimate.	Actual.			
CONCRETE.									
Cement.....	3 400	3 378	2.29	2.29	7 740	7 740			
Freight and loss on empties.....	bbl. 3 400	bbl. 3 378	.05	.037	170	125			
Tests.....	bbl. 3 400	bbl. 3 378	.025	.025	85	85			218
Sand.....	c. y. 850	c. y. 829	2.00	2.05	1 658	1 236	470		
Gravel.....	c. y. 1 500	c. y. 1 405	2.50	2.66	3 513	3 404	332		
Peastone.....	t. 50	t. 45.5	2.50	2.33	114	42	64		
Plant.....	\$ 2 300				13 280	12 632	866		
Estimated credit.....					2 100	4 249	100		249
FORMS.									
Form lumber.....	M 91	91	55.00	59.50	5 000	5 416			
Nails, oil and sundries.....	\$ 375				375	933	45		
Metal forms erected, No. 48.....	\$ 875				875	573	301		218
Estimated salvage on form lumber.....					800				
LUMBER.									
2" spruce plank.....	M 17	20.5	65.00	55.75	1 105		1 142		
3" plank.....	M 1 1/2	1.5	65.00	70.00	87		109		
3/4" furring 2 x 4 studding.....	\$ 50				50		89		
1" maple tongue and groove.....	M 10	10	92.00	93.00	920		930	170	
1" cork flooring.....	s. f. 68	68	.44	.155	30	11			
1" cell board, 135 s. f.....	\$ 50				50	32			
Building paper.....	roll 76	7	3.50	3.50	266		25		
					2 508	43	2 295		

orders. In the estimated quantity column is entered the total quantity as shown in the Analysis of Estimate and in the actual quantity column the quantity actually paid for. This statement is made to show as nearly as possible not only what the overrun is at the time the statement is made, but the final overrun or saving.

Of course, on the first three or four statements on a job that will take ten months to complete this is not possible, as all purchases will not be made or all contracts let, but in a very short time this comparison will indicate quite clearly the saving or overrun on the material costs that will show at the completion of the work. In addition to the outstanding orders being shown, we also estimate salvages and credits on plant, form lumber, etc., and include these figures in our statement.

Three copies of this monthly Material Statement are made. Two copies are sent the home office, — one for the general superintendent and one for the Cost Department. The third copy is for the job files.

We have, therefore, in the home office each week a Labor Cost Statement and each month a Material Cost Statement.

7. Tabulating Job Cost by the Graphic Method.

The purpose of this graphic chart is to place before the general superintendent and construction manager the status of the job and enable them to quickly pick out those items which are above the estimate and need special attention.

This chart shows what the final overrun or saving will be on the various items if the unit obtained to date is maintained for the remainder of the work.

A valuable feature of this chart is that the quantity of work influences the tabulation, thereby showing that a small overrun on a very large quantity would result in a much larger money overrun at the end of the job than a large overrun on a small quantity of work. This would indicate that the large quantities of work to be performed should have the first attention in getting low unit costs.

On our Labor Cost Statement you will remember we show the saving or overrun to date on the various items of work.



SECTION II.—FORM VIII.

Job No. 1145.

ABERTHAW CONSTRUCTION COMPANY.

COST SUMMARY.

MANUFACTURING BUILDING FOR E. A. MALLORY & SONS, INC., DANBURY, CONN.

Date started, 4-17-19. Date completed, 10-24-19.

ITEM.		Quantity.	LABOR.				
			Mix. Place.	Unl. Cem.	Unl. Agg.	Total Unit.	
CONCRETE.							
1	Footings, columns, floors, roof, etc.	c. y.	2 077	1.20	.338	.935	2.47
2	Window sills, coping, etc.	f. l.	1 548	.15	.0029	.021	.173
3	Carbo. rub, inside and outside.	s. f.	14 210	.143			.143
4	Granolithic finish, laid after.	s. f.	28 000	6.20	.29	.38	6.87
5	Unload and handle cinders.	\$					18.00
MASONRY.							
			Quantity.	Mix. Tend. Lay.	Unl. Cem.	Unl. Sand.	Total Unit.
6	Unload, mix mortar, tend and lay 4" x 6" T. C., part incl. stagings	s. f.	5 861	13.30	.12	.187	13.61
7	Plaster partitions and metal sash.	s. y.	1 291	.582	.018	.0077	.607
8	Picking second-floor ceiling for plaster.	s. y.	970	.098			.098
9	Plaster second-floor ceiling.	s. y.	970	.457			.457
10	Metal lath partitions.	\$					64.00
FORMS.							
			Quantity.	Make Erect Strip.	Unl. Lumb.		Total Unit.
11	Footings, foundations, brook wall, etc.	s. f.	16 808	7.98	.17		8.15
12	Floors, beams, curtain walls, etc.	s. f.	46 422	11.30	.17		11.47
13	Columns and mullions.	s. f.	7 852	17.90	.17		18.07
14	Sidewalk.	\$					47.00
15	Windows, coping, etc.	f. l.	1 590	.27	.0009		.2709
16	Brook wall under first floor.	\$					144.00
17	Tunnel walls.	\$					383.00
REINFORCEMENT.							
			Quantity.	Bend and Place.	Unl. and Team.		Total Unit.
18	Cut, bend and place, including spirals.	t.	84.74	14.99	2.29		1 728
EXCAVATION.							
			Quantity.				Total Unit.
19	Clear site.	\$					307.00
20	Dig footings, foundations, etc.	s. y.	1 742	1.06			1 06
21	Backfill.	\$					438.00
22	Sheeting.	\$					353.00
23	Coffer dam.	\$					652.00
CARPENTRY.							
			Quantity.	Labor Unit.			Total Unit.
24	Framing, temp. roof, etc.	M	31	16.95			16.95
25	Erect wood partitions, sash, doors, etc.	s. f.	3 330	.75			.75
26	Setting wood doors.	\$					742.00
27	Setting wood sash.	s. f.	3 784	.241			.241
28	Carpentry work — bulkhead.	\$					65.00

ABERTHAW CONSTRUCTION COMPANY.

COST SUMMARY.—CONTINUED.

Supt. John L. Noel

[illegible]

Any seemingly small unit overrun on this labor statement would not always cause serious comment on the part of the job superintendent or management, but on these charts this small unit overrun, if it applied to a large quantity of work, would result in a very large money loss at the end of the job.

Plotting these costs each week, directly under the previous weeks, shows any variations and can be easily studied, compared and acted upon immediately before it is ancient history and too late to do any good.

8. *Final Cost Summary.*

At the completion of the job and after all bills have been paid, the final cost summary is worked up. The labor, material and plant units are shown separately and each divided into two or more items, and the total unit and total cost obtained.

These summaries are blue-printed and a copy furnished the Estimating Department.

Attached to this summary is a Job History, giving information regarding —

- Personnel;
- Prices paid for cement, sand, brick, etc.;
- Nature of the soil;
- List of subcontractors;
- Wages paid labor;
- How concrete was distributed, whether by buggy or chutes;
- Number of towers and height, etc.

9. *Cost Comparisons.*

In order to stimulate interest among our foremen we have been making up at the home office weekly comparative cost statements showing the units obtained on various jobs for similar classes of work. On this comparison we show the bogey unit allowed each job on the items compared, the quantity done, and the unit obtained on the job. Under each job we show the superintendent and foremen's names, and the units below the estimate have a square around them, and the foreman showing the best performance as compared with his own estimated unit has a star opposite his name. We find that these comparisons arouse considerable interest and some rivalry.

The quantity man, of course, has to keep in very close touch with the timekeeping and cost departments. He reports the quantities under the symbols as shown on the Analysis of Estimate, and must keep these right up to date in order to insure the cost statement being completed promptly.

On small jobs the reporting of quantities will be done by the engineer, but on large operations one man will be assigned to this work alone. Without good accurate quantities up to date at all times the cost data are, of course, practically useless.

Does it pay?

You may say, "Well, this seems to be a good system, but does it pay?" I think it does.

On one job, recently, the brick costs were high compared with the estimated unit. It was found that masons were laying 1 100 to 1 200 brick a day, a good average for that particular class of work, so attention was given to the tending. It resulted in a rearrangement of the delivery of the brick to the elevator, and a very substantial saving on the unit per thousand. The costs showed this high unit at once, and afforded the means of rectifying it before it was too late.

On a large job in the South, last summer, the labor overrun was steadily increasing, and a detailed study of the costs was made. It was found that 60 per cent. of the overrun was in the form work, and further, that 80 per cent. of this 60 per cent. was in two items. You can readily see that this gave to the management a big advantage in showing them what to concentrate on. This they did, with the result that many thousands of dollars were saved and the curve showing the overrun flattened out, and remained practically so during the remainder of the work.

On one job the cost of laying maple flooring was running high. A man was set to watch the operation. The building had square interior as well as exterior columns, the corners of which had been chamfered by fitting a fillet in the column form. When the edge strip was fitted around these columns a small triangular piece was fitted into the chamfered space. Time

taken on this one operation showed that it added 20 cents per square over the whole floor, as there were four pieces fitted to each interior and two to each exterior column, or twelve to each bay. It was too late to make the maximum saving of 20 cents per square on this job, but by filling these holes with neat cement mortar the cost per square was reduced about 13 cents, and on the next similar building, by cutting off the fillet strip on a bevel just above the level of the edge strip, the full 20 cents per square was saved.

On another job the cost of laying floor plank was high. A time study was made and several reasons discovered for the high cost, one being the high cost of lumping, largely due to lack of proper planning. The cost prior to the time study was \$10 per thousand board feet. The time study showed that it could be done for \$5.25 if done at 100 per cent. efficiency. The final average for this job was \$8.65.

The above are some examples where the savings can actually be traced to our cost system. We feel that there are many other instances where savings are made and economies obtained and that if all contractors could establish some such system it would be of great advantage to all.

DISCUSSION.

LEONARD C. WASON.* — I think that Mr. Connor has proved most conclusively that it does pay. The company developed a cost accounting system at a very early date. The present system is the outgrowth of experience. Its first object is to give promptly information to the job superintendent wherein work is costing too* much, so that it can be quickly corrected. Its secondary object is to obtain accurate data for assisting in making future estimates of the cost of similar work.

I will cite one of our early contracts, twenty or more years ago, when dollars counted a great deal in the results accomplished.

* President, Aberthaw Construction Company, 27 School Street, Boston, Mass.

Before building the concrete fence around Harvard's Athletic Field, we made an estimate of cost of labor per lineal foot of posts above the horizontal beam at the ground level, of \$1.00 per lineal foot. The first week these were started the cost was \$2.40 per lineal foot. I had the report on Saturday morning, and when I went to pay off I called the attention of the foreman to this item. He said he was doing the best he could. I couldn't stop to look into it then, but on Monday morning I went over, spent the forenoon there, and gave him my ideas as to how he could straighten it out. The result was that the cost dropped to between fifty and sixty cents per lineal foot, and did not exceed the estimate again during the life of the job, which ran several months. Prompt action changed a loss into a profit without any loss in quality of work. The great thing is to check the work when you can act on what you find instead of when it has become ancient history.

I know one large local construction firm which has a most elaborate cost system, but they do not obtain their records until about three weeks after the work has progressed. It is then ancient history, — too late to act in order to correct expensive items.

Eight to twelve items, out of the fifty to seventy total into which our records are subdivided, include nearly 80 per cent. of the total cost of all operations. These are analyzed and on the superintendent's desk at ten o'clock on the morning following the execution, and he has all the rest of the day to act upon them, if necessary. So our costs enable him to keep the work under absolute control, and, thereby, savings are made.

I assure you most positively that it does pay. It paid several years ago when we were doing strictly lump-sum contract work, and it pays much more now on percentage work. It keeps the work under absolutely close control. It also keeps us on very friendly terms with the owner. I wish that more contractors did it. If they did there would be fewer failures and there would be more profits made in the contracting business.

To illustrate by one comparison before closing, as to the difference in cost between lump-sum bidding and percentage work. We have had two cases — one a very small contract and

one fairly sizable — where the owners received lump-sum bids and thought them rather high. They were strictly competitive bids from several contractors. They were rejected and we were awarded the contract on a cost-plus basis. We completed the small job about 4 per cent. under the lowest bid, and on the large job we saved over 10 per cent., showing that work on a percentage basis and with the cost under close control can be done cheaper than on the lump-sum contract basis.

MEMOIR OF DECEASED MEMBER.**LOUIS BERTRAND VAUGHAN.***

LOUIS BERTRAND VAUGHAN, the son of Andrew Jackson Vaughan and Esther Norris Vaughan, was born in Boston, Mass., August 22, 1858, and died at Providence, R. I., July 22, 1920. He came of New England ancestry and was a lineal descendant of George Vaughan, who had the commission of colonel in the provincial forces during Queen Anne's War and in 1715 was appointed lieutenant-governor of the province of New Hampshire.

Louis Bertrand Vaughan received his early education in a private school in Providence, R. I., and in 1878 was graduated from the English High School to take up engineering work in the city engineer's office in Providence.

From 1878 to May, 1886, he was engaged as rodman, instrumentman and assistant engineer in city property, sewer and highway departments, on surveys and on the construction of sewers and roads, for the city of Providence. For a short while after this, Mr. Vaughan engaged in private practice as a civil engineer in Providence, but left that in May, 1887, to take up cable railroad work. While engaged in this special field, he acted as assistant engineer for the Cable Tramway Company, of Omaha, Neb., first in immediate charge of construction of power house and installation of driving-plant, and second season in charge of surveys for and construction of cable roadway. From February, 1889, to April, 1890, Mr. Vaughan was assistant engineer with the Denver (Colorado) City Cable Railway Company, in charge of surveys for and construction of roadway of Larimer Street Line, and Larimer Street and 16th Street

* Memoir obtained by Frank E. Winsor and substantially as prepared for the American Society of Civil Engineers.

viaducts. The remainder of the year 1890 was spent in Cleveland, Ohio, with the City Cable Railway Company, in charge of construction of one division of road, including track and vault work.

In February, 1891, Mr. Vaughan was appointed assistant engineer of the Brooklyn (N. Y.) Heights Railway Company, in charge of the construction of the power house and installation of the plant, Montague Street Cable Road. From July, 1891, to April, 1893, he was assistant engineer on Broadway and Seventh Avenue Railway Company, New York City, in charge of construction of a section of the cable railway from Waverly Place to 17th Street, and later of the Houston Street Power Station, including the installation of driving machinery.

For a short time after this, Mr. Vaughan returned to private practice as a civil engineer in Providence. In April, 1895, he went to Cambridge, Mass., as assistant engineer in charge of the construction of several sections of the 2 500 000 000 gal. Hobbs' Brook Storage Basin of the water works, the last six months as resident engineer in entire charge of the completion of the work and of final estimates. This work was followed by a short period as assistant engineer in charge of the surveys for a section of a high-level sewer of the Massachusetts Metropolitan Sewerage Commission.

From December, 1898, to May, 1902, Mr. Vaughan was with the Boston Elevated Railway Company as assistant engineer on calculations for the steel structure, in charge of the construction of pile and concrete foundations on a section of the road, on design of special track work, and in charge of re-arrangement of tracks, installation of third rail and changes in station platforms of the Boston subway. During the last six months he was in the roadmaster's office, in charge of track repairs on the elevated structure and in the subway.

From May to September, 1902, he was with Westinghouse, Church, Kerr & Co., in charge of the surveys on a section of high-speed electric railroad in central New York state, but here his health broke down and he was obliged to resign.

For about three years after this, Mr. Vaughan was with Percy M. Blake, civil and hydraulic engineer. Newtonville,

Mass., as assistant engineer in charge of surveys, designs and estimates for water works and water-power development and valuation of water-works properties in various places in Massachusetts and Connecticut.

It was not until February, 1906, that he was connected with the Board of Water Supply, Reservoir Department, for New York City. At that time he was appointed assistant engineer in charge of the real-estate surveys. From 1909 to 1911 Mr. Vaughan was a section engineer in charge of the construction of the intercepting sewer in Kingston, N. Y. During 1912-13 he occupied a similar position on bridge construction for the highway around the reservoir, including the Travers Hollow bridge. In 1914 Mr. Vaughan was on the fencing and highway surfacing contracts around the reservoir.

In April, 1915, he was transferred to the Southern Aqueduct division at Valhalla, N. Y., where he was engaged on the final estimates for the Kensico Reservoir, including bridges and highways. On March 3, 1916, Mr. Vaughan retired from the engineering profession, to spend the remainder of his life in Kingston, N. Y.

On September 21, 1882, Mr. Vaughan was married to Miss Ida Etta Hall, of Providence, R. I. In the fall of 1918, after a year's sickness, Mrs. Vaughan died at Kingston, N. Y. From this blow Mr. Vaughan never recovered. Worn down by the grief and sorrow of her sickness and death, pernicious anemia did its deadly work, and in less than two years Louis Bertrand Vaughan died, at the home of his brother, in Providence, R. I. Here he was laid to rest beside his wife, in the North Burial Ground.

He is survived by a brother, Frank Leslie Vaughan, secretary and treasurer of the Providence Engineering Corporation, Providence, R. I., and an only son, Victor Hall Vaughan, a graduate of Harvard College, class of 1918.

From 1906, when Mr. Vaughan joined St. John's Episcopal Church in Kingston, N. Y., he held the various offices of vestryman, senior warden and church treasurer. At the time of his death he was senior deacon of Kingston Lodge, No. 10, F. & A. M.; a past high priest of Mount Horeb Chapter, R. A.,

Kingston; commander of Rondout Commandery, No. 52, Knights Templar, Kingston, N. Y., and a member of Cyprus Temple, Mystic Shrine, of Albany, N. Y. He was also a member of the American Society of Civil Engineers, New York City, and of the Boston Society of Civil Engineers.

Mr. Vaughan was a man of quiet nature and fond of home life. In his profession he was a diligent and conscientious worker, never allowing his own personal feelings and comfort to interfere with the carrying out of his duties and obligations. He was a wide reader, especially in the field of literature and history, and throughout his life was much of a scholar. To those who really knew him, his extraordinary kindness and devotion to high ideals gained him a name to be envied.

"A good name is rather to be chosen than great riches, and loving favour rather than silver and gold."



10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525
 526
 527
 528
 529
 530
 531
 532

ADVERTISEMENTS

BOSTON SOCIETY OF CIVIL ENGINEERS
FOUNDED 1848

INDEX TO ADVERTISERS.

	PAGE
A. B. SEE ELECTRIC ELEVATORS, 111 Devonshire St., Boston.....	VI
ABERTHAW CONSTRUCTION Co., 27 School St., Boston.....	XIV
ADAMS, H. S., 108 Ames Building, Boston, Mass.....	V
ASPINWALL & LINCOLN, 3 Hamilton Pl., Boston.....	V
ASSOCIATED ARCHITECTS PRINTING & SUPPLY Co., 21-27 Pearl St., Boston.....	XIV
BAY STATE DREDGING AND CONTRACTING Co., 62 Condor St., East Boston.....	XVIII
BEATTIE, ROY H., 10 Purchase St., Fall River.....	XIII
BETHLEHEM STEEL BRIDGE CORPORATION, Bethlehem, Pa.....	XVI
BISHOP, J. W., & Co., 683 Atlantic Ave., Boston.....	VI
BLAIR, ISAAC, & Co., Inc., 433 Harrison Ave., Boston.....	IV
COLEMAN BROS., 1 Marginal St., Chelsea.....	XIII
DONOGHUE, P. W., 170 Purchase St., Boston.....	XV
EARNSHAW, H. P. J.....	XIII
EASTERN BRIDGE AND STRUCTURAL Co., Worcester.....	XI
FAY, SPOFFORD & THORNDIKE, 15 Beacon St., Boston.....	V
FORT HILL PRESS, 176 High St., Boston.....	XIV
FULLER, GEORGE W., 170 Broadway, New York.....	V
GOW, CHARLES R. Co., THE, 166 Devonshire St., Boston.....	XII
HALL, JOHN G., & Co., 114 State St., Boston.....	XIII
HOLBROOK, CABOT & ROLLINS CORPN., 6 Beacon St., Boston.....	VIII
HOLZER, U., 25 Bromfield St., Boston.....	IX
HUGHES, EDWARD F., 8 Oliver St., Boston.....	XIII
LEDDER & PROBST, 21 Pearl St., Boston.....	XIII
LEY & Co., INC., FRED T., Springfield, Mass.....	III
MAIN, CHARLES T., 201 Devonshire St., Boston.....	IV
METCALF & EDDY, 14 Beacon St., Boston.....	V
NEW ENGLAND FOUNDATION Co., INC., 70 Kilby St., Boston.....	XIII
NEW ENGLAND SAND & GRAVEL Co., 161 Devonshire St., Boston..	IX
OLD CORNER BOOK STORE, 27 Bromfield St., Boston.....	XIII
PALMER, JOHN E., 1012 Old South Bldg., Boston.....	XIII
PENN METAL Co., 65 Franklin St., Boston.....	VI
PENNSYLVANIA CEMENT Co., 161 Devonshire St., Boston.....	XII
PERRIN, SEAMANS & Co., 57 Oliver St., Boston.....	IX



CAMP DEVENS WAS READY!

Army Cantonment at Ayer, Mass., Completed on Schedule Time

**Demonstrating the Wisdom of awarding this
Contract on a Cost Plus Percentage Basis**

The 622 Buildings whose completion our schedule called for by September 1 were ready for the troops, and many of them occupied.

And 124 Buildings in Addition, including 46 of the 59 buildings needed for the 1,000-bed hospital unit, costing \$500,000; refrigerating plants, storehouses, bakeries and miscellaneous buildings—all these completed ahead of schedule time.

Completing This \$6,000,000 Contract on Schedule Time Necessitated:

A Force of 9,000 Men
A Weekly Payroll of
\$400,000
\$750,000 in Ready Cash
Finishing One Building
Every Forty Minutes for
Two Months
The Delivery of 30 Million
Feet of Lumber

Unloading 50 Carloads of
Materials Daily

Building a Complete Water
Supply System with
20 Miles of Pipe

Building a Complete Sewer-
age System with
20 Miles of Pipe

Capt. Canfield, in command of the Ayer Camp, informing us that Ayer headed the list of cantonments in percentage of completion, writes:

*"This distinction should be a source of great gratification to
your organization, as it is to mine."*

FRED T. LEY & CO., Inc.

Contractors

BOSTON

SPRINGFIELD

NEW YORK

	PAGE
RAYMOND CONCRETE PILE Co., 80 Boylston St., Boston.....	XVII
RIDEOUT, CHANDLER & JOYCE, 178 High St., Boston.....	XIII
ROCKPORT GRANITE Co., Rockport, Mass.....	VII
SIMPSON BROS. CORPN., 77 Summer St., Boston.....	VII
SMITH, B. F., & Co., Merchants Bank Building, 79 Milk St., Boston	XIII
STONE & WEBSTER, 147 Milk St., Boston.....	X
STUART, T., & SON Co., Newton, Mass.....	XVIII
THOMPSON, SANFORD E., 136 Federal St., Boston.....	V
THORPE, LEWIS D., 201 Devonshire St., Boston.....	V
TUCKER, EDWARD A., Co., 101 Milk St., Boston.....	VII
TURNER CONSTRUCTION COMPANY, 178 Tremont St., Boston.....	XV
WALDO BROTHERS AND BOND Co., 181 Congress St., Boston.....	XI
WARREN FOUNDRY AND MACHINE Co., 11 Broadway, New York...	IX
WESTON & SAMPSON, 14 Beacon St., Boston.....	V
WHITMAN & HOWARD, 220 Devonshire St., Boston.....	V
WORCESTER, J. R., & Co., 79 Milk St., Boston.....	V

GEO. A. BLAIR

L. L. STREET

W. O. WELLINGTON

ISAAC BLAIR & CO., Inc., General Contractors

Shoring and Moving Buildings a Specialty

433 Harrison Avenue, BOSTON

PROFESSIONAL CARDS

CHAS. T. MAIN

ENGINEER

201 Devonshire Street, Boston, Mass.

Rooms 817-833

Plans and Specifications for the erection and equip-
ment or reorganization of textile mills and other
industrial plants, including steam and
water-power plants

H. S. ADAMS**Consulting Engineer**

**108-9 AMES BUILDING
BOSTON, MASS.**

SANFORD E. THOMPSON

M. Am. Soc. C. E. M. Am. Soc. M. E.

Consulting Engineer

Design of Steel and Reinforced Concrete;
Review of Plans; Estimates and Appraisals;
Tests of Cement and Concrete; Organization of
Construction and Industrial Work.

**OFFICES AND LABORATORY
136 FEDERAL STREET, BOSTON**

ASPINWALL & LINCOLN**Civil Engineers**

**3 HAMILTON PLACE
BOSTON**

LEWIS D. THORPE**Civil and Sanitary Engineer**

Water Works, Sewerage and Sewage
Disposal

Supervision of Construction and Operation

**201 Devonshire Street
BOSTON, MASS.**

FAY, SPOFFORD & THORNDIKE
Consulting Engineers

**BRIDGES AND OTHER STRUCTURES OF
STEEL AND MASONRY. FOUNDATIONS.
RIVER AND HARBOR WORKS**

FREDERIC H. FAY CHARLES M. SPOFFORD
STURGIS H. THORNDIKE

15 Beacon Street, Boston, Mass.

WESTON & SAMPSON

ROBERT SPURR WESTON G. A. SAMPSON

Laboratory for the Analysis of Water,
Sewage, Filtering Materials, etc., Design,
Inspection and Supervision of Water Puri-
fication and Sewage Disposal Plants.

14 BEACON STREET, BOSTON, MASS.

GEORGE W. FULLER

M. Am. Soc. C. E. M. Am. Inst. Cons. E.

Consulting Hydraulic Engineer and Sanitary Expert

JAMES R. McCLINTOCK

Water Supply and Purification, Sewerage and
Drainage, Disposal of Sewage and Refuse,
Investigation of Epidemics, Public Utilities
Valuations, Supervision of Construction and
Operation.

170 Broadway, New York, N. Y.

WHITMAN & HOWARD**Civil Engineers**

(Established in 1869)

**220 Devonshire Street Room 504
BOSTON**

J. E. Worcester E. E. Pettes G. H. Brazier
MEMBERS OF AM. SOC. C. E.

J. R. WORCESTER & CO.**Consulting and Designing
Engineers**

Bridges Foundations
Steel and Reinforced Concrete Construction

79 MILK STREET, BOSTON

Cement Testing Laboratory at Waltham, Mass.

METCALF & EDDY

Leonard Metcalf Harrison P. Eddy
Charles W. Sherman Almon L. Fales
Frank A. Marston

CONSULTING ENGINEERS

Water Supply and Sewerage

14 BEACON ST. BOSTON, MASS.

NEW YORK
101 PARK AVENUE

BOSTON
683 ATLANTIC AVENUE

J. W. BISHOP COMPANY

GENERAL CONTRACTORS

PROVIDENCE
617 BUTLER EXCHANGE

WORCESTER
109 FOSTER STREET

More than 50 Years of Service

METAL LATH
CORNER BEAD
CONCRETE REINFORCEMENT
METAL ROOFING AND SIDING
CULVERT PIPE
BOXES, TANKS, LOCKERS
BINS, SHELVING, PARTITIONS
AND ALL FORMS OF
SHEET METAL, STAMPED,
FORMED OR WELDED

USE HAMPTON METAL
"IT WATCHES OTHERS RUST"

Penn Metal Company
65 Franklin Street
Boston, Mass.

OFFICE AND FACTORIES
BOSTON JERSEY CITY PHILADELPHIA
PORTLAND, MAINE

A. B. SEE ELECTRIC ELEVATORS

Established 1883

ELECTRIC ELEVATORS OF ALL TYPES

OFFICES

New York
Boston
Hartford
Jersey City
Philadelphia
Washington
Baltimore
Cleveland
Montreal
Toronto

WORKS

Jersey City
New Jersey
Montreal
Canada

BOSTON OFFICE

Minot Building
111 Devonshire St.

SIMPSON BROS. CORPORATION

ENGINEERS AND CONTRACTORS

FOR

REINFORCED CONCRETE
CONSTRUCTION

HASSAM CONCRETE STREET PAVEMENT



ROCKPORT GRANITE

*permanently resists all
action of Sea Water*

It is an undeniable fact that chemical changes take place in the cement of CONCRETE construction exposed for any number of years to sea water, changes that are certainly not for the better.

No changes take place in Rockport Granite. It is permanent, and it is impermeable; and these FACTS are beyond question. The same facts apply to masonry work of every description—Rockport Granite is the ONE material of PERMANENCY.

A combination of Quality and Low Price is offered in Rockport Granite, full details of which will be supplied upon request. Write.

ROCKPORT GRANITE CO. - **Rockport, Mass.**
C. HARRY ROGERS, Treas. and Gen'l Mgr.

Branch Offices

Boston, New York City, Chicago, Detroit, Cleveland and Philadelphia

EDWARD A. TUCKER COMPANY

Concrete Engineers

Designs and Estimates Submitted for Concrete Reinforcement—Monotype Deformed Bars—Spirals—Metal Forms

CONVERSE BUILDING, 101 MILK STREET, BOSTON

Direct Mill Connections

Warehouse, Cambridge

Shop, Camden, N. J.

Telephone, Fort Hill 1840

Please mention the Journal when writing to Advertisers

Holbrook, Cabot & Rollins Corp'n

Contractors

Heavy Masonry and Concrete Construction, Deep Foundations

6 BEACON STREET BOSTON, MASS.

**52 Vanderbilt Avenue
New York, N. Y.**

J. W. ROLLINS, President
T. B. BRYSON, Vice-President
A. P. HOOVER, Vice-President
W. S. PATTEN, Treasurer

NEW ENGLAND SAND AND GRAVEL CO.

161 DEVONSHIRE ST.

BOSTON, MASS.

SCREENED, SIZED AND WASHED

BANK SAND AND GRAVEL

ONE CAR OR A TRAINLOAD

CONCRETING, GRANOLITHIC AND ROOFING GRAVEL

BUILDING AND CONCRETE SAND

PROMPT AND RELIABLE SERVICE

WARREN FOUNDRY AND MACHINE CO.

MANUFACTURERS OF

Cast Iron Gas and Water Pipe

FLANGE PIPE

SPECIAL CASTINGS

201 Devonshire St.,
BOSTON, MASS.

SALES
OFFICES

11 Broadway,
NEW YORK

PERRIN, SEAMANS & CO.

Machinery, Tools and Supplies

FOR

Construction Work

57 OLIVER STREET, BOSTON

U. HOLZER, BOOK-BINDER

25 BROMFIELD ST., BOSTON, MASS.

ESTABLISHED 1870.

All kinds of Books bound and repaired.

Maps and Charts mounted.

Portfolios, Scrap Books, Blank Books, etc., made to order.

Lettering in Gold; Paper-Splitting; Inlaying; etc.

Photographs Mounted on Card or Paper without Cockling.

Telephone
and
Elevator

Please mention the Journal when writing to Advertisers



STONE & WEBSTER

Incorporated

DESIGN steam power stations, hydro-electric developments, transmission lines, city and interurban railways, gas and chemical plants, industrial plants, warehouses and buildings.

CONSTRUCT either from their own designs or from designs of other engineers or architects.

MANAGE public utility and industrial companies.

REPORT on going concerns, proposed extensions and new projects.

FINANCE industrial and public utility properties and conduct an investment banking business.

NEW YORK

BOSTON

CHICAGO

EASTERN BRIDGE



— AND —



STRUCTURAL CO.

Worcester, Massachusetts,

For Prices on all Classes of

STEEL AND IRON WORK.

WE DESIGN AND MANUFACTURE

**ROOF TRUSSES, GIRDERS, COLUMNS, STAIRS
AND FIRE ESCAPES FOR BUILDINGS**

FOOT BRIDGES, HIGHWAY BRIDGES, RAILROAD BRIDGES

**We Carry a Large Stock of
I-BEAMS, PLATES AND ANGLES**

Can Make Quick Deliveries.   Send in Your Inquiries.

WALDO BROS. AND BOND COMPANY

**Building Material and
Construction Equipment**

181 CONGRESS STREET, BOSTON, MASS.

THE EXTREME HIGH QUALITY OF
PENNSYLVANIA PORTLAND CEMENT

MAKES ITS USE ESSENTIAL WHERE
WORK OF THE HIGHEST CLASS IS DESIRED

PENNSYLVANIA CEMENT CO.

NEW YORK OFFICE
30 East 42d St.

BOSTON OFFICE
161 Devonshire St.

THE CHARLES R. GOW COMPANY
Contractors for Engineering Construction
No. 166 DEVONSHIRE STREET
BOSTON, MASS.

EDWARD F. HUGHES
Artesian and Driven Wells

for
Manufacturing, Public or Private
Water Supply

954 Oliver Building, 8 Oliver Street, Boston, Mass.
TEL. 1633 MAIN

SCIENTIFIC BOOKS
AND PERIODICALS

THE OLD CORNER BOOK STORE
27-29 Bromfield Street
BOSTON, MASS.



Rentals with Expert Operators a Specialty

JOHN G. HALL & CO.

114 STATE STREET, BOSTON

=PILING=

JOHN E. PALMER
Contracting Engineer

Contractor for Sewers, Water Works,
Concrete Bridges, Concrete
Foundations, etc.

Room 1012, Old South Building
Boston, Mass.

Telephone, Fort Hill 1731

LEDDER & PROBST, Inc.
21 PEARL STREET, BOSTON (9), MASS.

Surveying Instruments
REPAIRING
BLUE AND BLACK PRINTS

Drawing Materials

B. F. SMITH & CO., INC.

ESTABLISHED 1878

Engineers and Contractors
ARTESIAN AND DRIVEN WELLS
FOUNDATION BORINGS

79 MILK STREET
BOSTON, MASS.

RIDEOUT, CHANDLER & JOYCE

Engineers and Piping Contractors

178 HIGH STREET - BOSTON, MASS.

Steam Specialties, Engineers' Supplies
Piping of All Kinds Furnished or Erected

New England Foundation Co., Inc.

Engineering and Construction
Simplex Concrete Piles

70 KILBY STREET :: :: BOSTON, MASS.

ROY H. BEATTIE

Harbor Improvements
Divers :: Lighters

10 PURCHASE STREET
FALL RIVER, MASS.

COLEMAN BROS.

General Contractors

Main Office

1 Marginal St.,
Chelsea

Boston Address

166 Devonshire St.

Associated Architects Printing & Supply Co.

NEW LOCATION

BETTER AND LARGER QUARTERS

21-27 Pearl Street, Boston

BLUE, BLACK AND VANDYKE PRINTS

GELITHO REPRODUCTIONS

SUPPLIES

Telephones, Main 8482 and 8483, Connecting All Departments

ESTABLISHED 1881



Our Motto
Quality and Service

SAMUEL USHER

BOOK : JOB : MAGAZINE : CATALOGUE

SCHOOL : LAW

PRINTING

DESIGNING ENGRAVING

TELEPHONE CONNECTION

176 TO 184 HIGH ST., BOSTON

Knowledge of

Engineering Design
Estimating
Planning of Operations
Purchase and Supply
Labor and its Right Guidance
Cost Accounting
Essential Control

Combined in a single homogeneous organization, adequately financed, is the

POWER behind ABERTHAW ACCOMPLISHMENT

ABERTHAW CONSTRUCTION COMPANY

BOSTON MASSACHUSETTS

ATLANTA

PHILADELPHIA

BUFFALO

6-94



Lockwood, Greene & Co., Architects

NATIONAL SPUN SILK CO., New Bedford, Mass.

230,850 sq. ft.

Turner Construction Company

178 Tremont St., Boston, Mass.

"Turner for Concrete"

Atlanta — Buffalo

New York — Philadelphia

P. W. DONOGHUE

Plumbing Contractor

FOR THE

\$28,000,000

Boston Army Supply Base

170 Purchase Street

BOSTON, MASS.

Telephone: Fort Hill 4974

Bethlehem Steel Bridge Corporation

BETHLEHEM, PA.

Design

Fabricate

Erect

STEEL BRIDGES and other Steel Structures

OFFICES:

NEW YORK, N. Y.

111 Broadway

PITTSBURGH

First Nat. Bank Bldg.

BOSTON

141 Milk Street

CLEVELAND

1525 Guardian Bldg.

PHILADELPHIA

Morris Building

CHICAGO


Peoples Gas Bldg.

ATLANTA

Candler Building

SAN FRANCISCO

Monadnock Bldg.



THE
RAYMOND METHOD
 of
Concrete Pile Installation

was chosen by the Engineers for the ARMY SUPPLY BASES at BOSTON, NEW YORK and NEW ORLEANS, because it makes absolutely certain that each and every concrete pile is perfect. A spirally reinforced steel shell is driven by a driving core, or mandrel. The core is then collapsed and withdrawn, leaving the shell in the ground. The interior of this shell may then be inspected; and finally the concrete is poured into it, the shell remaining in place to protect the pile column. ¶ We also construct Special Reinforced Concrete Work of every description: Shipbuilding, Ways, Docks, Bridges, Retaining Walls, Piers, Ore Handling Structures, etc.

RAYMOND CONCRETE PILE COMPANY

NEW YORK: 140 Cedar Street CHICAGO: 111 W. Monroe Street
 MONTREAL, CANADA: Raymond Concrete Pile Co., Limited
 BOSTON: 80 Boylston Street

A Form for Every Pile

A Pile for Every Purpose

T. Stuart & Son Company

General Contractors



NEWTON, MASSACHUSETTS

Bay State Dredging & Contracting Co.

Contractors

**River and Harbor Improvements,
Sea Walls, Breakwaters, Heavy
Masonry Construction.**

62 Condor St., East Boston, Mass. .

JAMES E. CASHMAN, Treas.

GORHAM H. WHITNEY, Prest. DAVID J. WHITE, Sec'y—Gen. Mgr.

SPECIAL COMMITTEES

ON THE LIBRARY

RICHARD K. HALE, Acting-Secretary, Chairman
EDWARD H. ROCKWELL FRANK A. MARSTON

ON MEMBERSHIP

JOHN E. L. MONAGHAN, Chairman
WALTER A. WOODS ARTHUR D. WESTON
HOWARD B. LUTHER WILLIAM P. MORSE
LEWIS J. JOHNSON FRANK B. WALKER

ON PUBLICATION

RICHARD K. HALE, Chairman
HAROLD K. BARROWS HENRY B. WOOD

ON PAPERS AND PROGRAMS

ROBERT SPURR WESTON, Chairman, ex officio
CHARLES M. SPOFFORD EDGAR S. DORR
JOHN E. CARTY KARL R. KENNISON
RALPH E. RICE FRANK B. WALKER
RICHARD K. HALE, Acting Secretary

ON SOCIAL ACTIVITIES

HARRISON P. EDDY, Jr., Chairman
HOWARD C. THOMAS ARMAND W. BENOIT
JOHN M. CASHMAN ERWIN HARSCH
SCOTT KEITH

RATES FOR ADVERTISEMENTS

For one year — 10 issues

One page	\$75.00
One-half page	40.00
One-quarter page	25.00
One-sixth page	17.50
One-eighth page	14.00
One-twelfth page	10.00

Last page, 50 per cent. additional.

For further information, or for contract forms, address

WILLIAM L. BUTCHER, Editor
715 Tremont Temple, Boston

